

The 46' Accu-Steel Cattle Building with PreCast Foundations



The Accu-Steel Cattle Building has been designed specifically to provide a dry, managed environment with excellent air quality to unlock cattle's potential from young calves to finish weight. Accu-Steel's unique features will provide you with reduced bedding needs and decreased labor requirements, while delivering nutrient-dense dry manure to increase your daily gains and accelerate your time to market.

- Managed environment for less animal stress - cattle stay cool in the summer, dry all year
- A full **46'** wide to give producers management options on head density and bunk space
- Reduced manure management and labor costs with a dry deep bedding pack
- 14 oz. Accu-Keder Cover - Individual cover per building bay – 15 year warranty* See for details
 - Most weather secure connection between truss and cover in industry
- Fully engineered building and PreCast foundation – USDA/NRCS/EQIP Compliant
- **PreCast 6' L panel wall & PreCast Accu Bunk save money compared to traditional foundations**
- 5' Bunk Eave - Wide enough to protect the bunk from rain and snow
 - Tall enough for equipment to safely pass under
- Ridge vent designed to work with building eaves to provide excellent air quality
- Air Management Tools - Optional end walls with 2 way gather doors and optional side curtains
- 2' Curtain Eave - Pushes water away from the building , bedding, and cattle
 - Maintains air quality even when optional curtain is raised
- Hot Dipped Galvanized steel for maximum corrosion protection
- Accu-Steel Factory Service and Installation - **PreCast foundation saves on installation Labor**
- Accu-Steel Inc. is a family owned company - Proudly designed and manufactured in Iowa

Managed Environment + Lower Costs + Faster Gains = Higher Returns

For more information:

www.asicoverbuildings.com

sales@asicoverbuildings.com

1-877-338-6936

Name:	
Location:	
Phone:	Fax:
Cell:	Coating: HOT DIP GALV.
Rafter Centers: 15'	Cover Spec: 14oz. KEDER
Building Length: .	Arc Length: 65'
Foundation: PRECAST SUPER BUNKS & 6' L-PANELS	

46' CATTLE BUILDING

SECTION VIEW PRECAST

Notes: KEDER COVERS ARE ATTACHED TO EACH RAFTER WITH AN ALUMINUM EXTRUSION. KEDER COVERS ARE TERMINATED ON THE CONTINUOUS EAVE RUB RAIL.

THIS DOCUMENT CONTAINS INFORMATION PROPRIETARY TO ACCU-STEEL INC. IT SHALL NOT BE REPRODUCED, USED, OR DISCLOSED WITHOUT PRIOR WRITTEN PERMISSION OF ACCU-STEEL INC.



Date: MAY 9, 2009
Project Name: 46' CATTLE
Drawn By: JCO
Sales #

1-877-338-6936 - P.O. BOX 201
 TEMPLETON, IA 51463
 Fax: 712-683-5512

